

ARCHTECH INDUSTRIES

CEBU OFFICE: YELLOW BELL LOWER CAYAM ST., RLJB PUROK 18, COLON, CITY OF NAGA, 6037 DAVAO OFFICE: BLK 5, MAGSAYSAY, CARMEN, DAVAO DEL NORTE PHONE NO.: 0965-196-8377 / 0969-193-8522 TEL. NO.: (032) 344-4199

EMAIL: ARCHTECHPHIL@GMAIL.COM

PROJECT: LOCATION:

TAGBILARAN BOHOL (UNTAGA PIGGERY) ALTURAS

Date:

MAY 27, 2024

To:

Henry D. Baliar

Item	VEX.	THE REPORT OF THE PARTY OF THE	model	Qty	Unit	Materials		The second
		Scope of Works				Unit Rate	Amount	Amount
1	PRELIM	INARIES						Toma Billion of
I.A	MOBILI	MOBILIZATION AND DEMOBILIZATION						
	I.A.1	DELIVERY CHARGE		1	lot			9,000.0
		Subtotal : Preliminaries						9,000.0
11	APOLI	LO CONVENTIONAL CONTROL PANEL OPTION 1						
II.A	II.A.1	Sigma CP - 4 Zone conventional fire alarm control panel 4 x Monitored detection zones compatible with many conventional detection devices, 2 x Monitored sounder outputs - 500mA per output, VFCO outputs 1A @ 30V DC (Fire, Local Fire & Fault), Configurable for use with I.S. devices and safety barriers, Integral 3 Amp PSU, Space for 2 x 12V 7Ah SLA batteries M2 Surface mount enclosure 385mm (W) x 310mm (H) x 90mm (D) (Made in UK) (2 years warranty	K11040 M2	2	Unit	28,640.00	57,280.00	57,280.00
	II.A.2	Back-up Battery (1 year warranty)	12V 7.2AH YUASA	2	pc/s	2,390.00	4,780.00	4,780.0
	II.A.3	D-128 Resettable call point (Red) Made in Malaysia (1 year warranty)	D-128	84	pc/s	492.00	41,328.00	41,328.0
	II.A.4	DEMCO SOUNDER AND STROBE LIGHT COMBINED (1 year warranty)	D-115/154L	88	pc/s	1,575.00	138,600.00	138,600.0
	II.A.5	Fire Alarm Terminal Block		4	pc/s	55.00	220.00	220.0
	II.A.6	Power Booster	Not included	THE ST				s in expelling all in
	II.A.7	REMOTE ANNUCIATOR	N/A		pc/s			
	II.A.8	TF WIRE 1.25mm # 16 2 core (Thermoplastic Fixture)	PHILFLEX	35	Roll	4.715.00	165,025.00	165,025.0
	nty is nu	(recommneded to use for protection against voltage fluctuations and surge voltage) Il and void unless the equipment pass through an appropriate Surge Protector and UPS as						
	II.A.9	Surge Protection	Surge Protector	1	pc/s	10.098.00	10,098.00	10,098.0
	II.A.10	1000VA 230V AVR Universal Sockets	UPS 1KVA	1	pc/s	/2,705.00	12, 05.00	12,705.0
	II.A.11	System programming, configuration, testing and commissioning	Not included			/ - 1		-
0	SUB T	OTAL FOR SUPPLY & DELIVERY OF APOLLO CONVENTIONAL CONTROL PANEL & ES				(, 0)	2	430,036.0

52,684.32 Total price 491,720.32

Payment:

Deposit Payment at Arch Tech Industries OPC, SECURITY BANK Account No. 000-0006061-9692

Deposit Payment at ARCHTECH PHIL FIRE PROTECTION SERVICES, SECURITY BANK Account No. 000-048390-450

Terms & Conditions:

- 1. Bank transfer or Cash upon pick up
- 2. 50% Downpayment for Order basis items to proceed Purchase Order
- 3. Purchased outside any Branch : Payment first before shipment
- 4. Restocking Fee of 40% of the Total Amount of the cancelled P.O will be charged to client.
- 5. No reservation for the complete items based on the PO. In case of 50% payment was received 7 working days is allowed to pick up the items.

Prepared by:

0955 - 196 8377